



PHASE TWO work indicated thus. All other information is Phase One, under construction, and is for reference only. Coordinate all PHASE TWO activity with Dolar Corp., Phase One General Contractor.

- ELECTRICAL NOTES**
- 1/2" C. 6 #12 (PWR) & 6 #18 (CONTROL)
 - 1/2" C. 4 #12 (PWR) & 4 #18 (CONTROL)
 - 1/2" C. 2 #12 (PWR) & 2 #18 (CONTROL)
 - 3/4" C. 6 #18 (PWR) & 6 #18 (CONTROL) & 2 #18 SHIELDED (LIGHT SENSOR)
 - 1/2" C. 2 #18 SHIELDED (LIGHT SENSOR)
 - 1/2" C. 2 #12 (PWR) & 2 #18 (CONTROL) & 2 #18 SHIELDED (LIGHT SENSOR)
 - 3/4" C. 4 #12 (PWR) & 4 #18 (CONTROL) & 2 #18 SHIELDED (LIGHT SENSOR)
 - RUN CONDUIT CONCEALED IN TOPPING ON SLAB ABOVE.
 - 1" C. 6 #12 (PWR) & 6 #18 (CONTROL) & 2 #18 SHIELDED (LIGHT SENSOR)

NOTE: CONTRACTOR SHALL NOT ACTIVATE DIMMER SYSTEM. FINAL CONNECTIONS SHALL BE CHECKED & SYSTEM SHALL BE ACTIVATED ONLY BY DIRECTION OF DIMMER SUPPLIER.

GENERAL NOTES:
 a) ELECT. CONTRACTOR SHALL COORDINATE LIGHTING LAYOUT WITH SPRINKLER LOCATIONS.

FIRST FLOOR LIGHTING PLAN — ACTIVITY CENTER
 SCALE 1/16" = 1'-0"

SECOND FLOOR & CATWALK LIGHTING PLAN — ACTIVITY CENTER
 SCALE 1/16" = 1'-0"

KEY PLAN
 NO SCALE

Sövik MATHRE SATHRUM QUANBECK ARCHITECTS PLANNERS | 205 South Water Street | Box 390 | Northfield Minnesota 55057 | 507-645-4461 | 612-336-8679
Phase Two
 St. Cloud State University
 St. Paul, Minnesota 55101
 Account I.D. No. 034304
 REGISTERED PROFESSIONAL ENGINEER
 ROMULO M. G. WILLIAR
 STATE OF MINNESOTA
 NUMBER 6372
 PHASE TWO
E2.1
 Revisions
 CONSULTANT
WAKSMA
 WAKSMA
 Lundquist, Wilmer, Schultz and Martin
 ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM THE CONSULTANT.
 Signature Date: [blank]
 Job No. 1105
 Checked: [blank] Date: [blank]
 Drawn: PEG

